BRUHAT BANGALORE MAHANAGARA PALIKE

Office of the Executive Engineer, Rajarajeshwari Nagara Division, RR Nagara Zone, B.B.M.P., Bangalore.

Tender Notification No: EE/RRND/Tend/20/2020-21 Date: 29.03.2021

Indent No: BBMP/2020-21/RD/WORK_INDENT42851/CALL-2

SCHEDULE -B

Name of Work: Maintenance of Road and Footpath in J P Park in ward no 17

Sl. No	Qty	Description of work	Unit	In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	190.08	Removing & Refixing stone slabs of drains and pointing in C.M (1:3).	Sqm	115.00	Rupees One Hundred Fifteen Only
2	72.00	KSRB 2-1 : Earthwork in surface excavation for levelling and lowering the ground manually (Other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift up to 1.5m, excavated surface levelled and neatly dressed, disposed earth to be levelled including breaking of clods and neatly dressed as per specifications.	Cum	272.00	Rupees Two Hundred Seventy Two Only
3	20.16	KSRB 4-1.3 : Providing and laying in position plain cement concrete of Mix 1:4:8 with OPC @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM curing complete as per specifications.	Cum	5570.00	Rupees Five Thousand Five Hundred Seventy Only
4	230.40	KSRB 5-14: Providing and constructing load bearing wall with solid concrete blocks having block density not less than 1800kg/m3 having a minimum average compressive strength of 4.00 N/mm2 confirming to IS 2185 (Part 1):2005 and constructed with CM 1:4, as per IS 2572:2005 including cost of all materials labour charges, scaffolding, curing, hire charges of machineries etc., complete as per specifications. KBS No.5.4 with solid concrete blocks of size 400x200x200mm	Sqm	1050.00	Rupees One Thousand Fifty Only
5	8.64	KSRB 4-1.6 ; Providing and laying in position plain cement concrete of Mix 1:2:4 with OPC @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregtes @ 0.53cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM curing complete as per specifications.	Cum	6050.00	Rupees Six Thousand Fifty Only
6	126.72	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete. 10 cms thick	Sqm	996.00	Rupees Nine Hundred Ninety Six Only
7	1728.00	KSRB 5-9 : Providing chamfering edges to stone slab 2.5 cms. Wide as per specifications. (only chamfered length shall be recorded)	Mtrs	63.00	Rupees Sixty Three Only

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP

8	288.00	KSRB 5-8.1 : Providing one line dressing to granite stone slab/granite stone masonry as per specifications.	Sqm	979.00	Rupees Nine Hundred Seventy Nine Only
9	640.00	Providing and fixing Pre cast solid concrete kerb stones made out of CC 1:2:4 and finished with CM 1:3 plastering and finishing cutting etc., complete. of size 450 x 200 x 400 mm	Nos	491.00	Rupees Four Hundred Ninety One Only
10	100.80	KSRB 15-13.1 : Providing and applying one coat distemper primer of approved brand on wall surface after throughly brooming the surface to remove all dirt, dust, mortar drops and other foreign matter including preparing the surface, even and sand paper smooth, cost of materials, labour, complete as per specifications. wall surface	Sqm	38.00	Rupees Thirty Eight Only
11	100.80	KSRRB 800-1. Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications.	Sqm	87.00	Rupees Eighty Seven Only
12	72.00	KSRRB M100-1 Loading and Unloading of Stone Boulder / Stone aggregates /Sand/ Kanker / Moorum. KSRRB M100-1 : Placing tipper at loading point, loading with front end loader,dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications. MORTH - 100/ Chapter 1.	Cum	98.00	Rupees Ninety Eight Only

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP